



**GENERAL NOTES FOR ALL DETAILS:**

- All concrete shall be commercial grade concrete.
- Inlet base may be cast-in-place or precast. Where precast inlet base is used as an alternate, a 4" compacted leveling bed of sand or 1/4"-0 crushed aggregate shall be provided.
- See Std. Drgs. RD372 for inlet top details.
- See Std. Drg. RD336 for tracer wire details, or approved alternate.
- See Std. Drgs. RD700 & RD701 for curb and gutter details.
- See Std. Drg. RD364 for subgrade drain details.
- Provide sump only where shown on plans, and allowed by jurisdiction. For sump details, see Std. Drg. RD364.
- Location, elevation, and number of pipe(s) varies.

**NOTE:** This detail has been modified by the City of Winston. All material and workmanship shall be in accordance with the current Oregon Standard Specifications.

**WINSTON STANDARD DRAWINGS**

**CONCRETE INLET BASE**  
TYPE CG-3

RD371-W