



NOTES:

1. CONSTRUCT EXPANSION JOINTS AT 200' MAXIMUM SPACING AND AT POINTS OF TANGENCY.
2. CONSTRUCT CONTRACTION JOINTS AT 15' MAXIMUM SPACING.
3. WHEN BONDING TO DENSE GRADED AC, APPLY EPOXY CEMENT BETWEEN SURFACES.

NOTES:

1. THIS DETAIL HAS BEEN MODIFIED BY THE CITY OF WINSTON. ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE CURRENT OREGON STANDARD SPECIFICATIONS.



WINSTON STANDARD DRAWING

DRAINAGE CURBS